Project Verification Report

2021

COVER PAGE

Project Verification Report Form (VR)						
BASIC INFORMATION	BASIC INFORMATION					
Name of approved UCR Project Verifier / Reference No.	Mr. Pankaj Kumar					
Type of Accreditation	☑ CDM or other GHG					
Approved UCR Scopes and GHG Sectoral scopes for Project Verification	01 Energy industries (Renewable/Non- Renewable Sources)					
Validity of UCR approval of Verifier	December 2023					
Completion date of this VR	25/08/2023					
Title of the project activity	14.2 MW Wind Project in Karnataka					
Project reference no. (as provided by UCR Program)	241					
Name of Entity requesting verification service (can be Project Owners themselves or any Entity having authorization of Project Owners, example aggregator.)	UCR ID – 241 Kosher Climate India Private Limited Name: Narendra Kumar Email ID – narendra@kosherclimat e.com					
Contact details of the representative of the Entity, requesting verification service (Focal Point assigned for all communications)	UCR ID – 241 Kosher Climate India Private Limited Name: Narendra Kumar Email ID – narendra@koshercl imate.com					
Country where project is located	India					
Applied methodologies (approved methodologies by UCR Standard used)	Applied Baseline Methodology: AMS-I.D.: "Grid connected renewable electricity generation", version 18.0					

	Standardized Methodology: Not Applicable
GHG Sectoral scopes linked to the applied methodologies	01 Energy industries (Renewable/Non- Renewable Sources)
Project Verification Criteria: Mandatory requirements to be assessed	✓ UCR Standard✓ ApplicableApprovedMethodology
	Applicable Legal requirements /rules of host country
	Eligibility of the Project Type
	Start date of the Project activity
	Meet applicability conditions in the applied methodology
	☑ Credible Baseline☑ Do No Harm Test
	Emission Reduction calculations
	☑ Monitoring Report☑ No GHG Double Counting
	Others (please mention below)
Project Verification Criteria: Optional requirements to be assessed	Environmental Safeguards Standard and do- no-harm criteria
	Social Safeguards Standard do-no- harm criteria
Project Verifier's Confirmation: The UCR Project Verifier has verified the UCR project activity and therefore confirms the following:	The UCR Project Verifier [Mr. Pankaj Kumar], certifies the following with respect to the UCR Project Activity [14.2 MW Wind Project in Karnataka].

The Project Owner has correctly described the Project Activity in the Project Concept Note (dated 02/08/2022) including the applicability of the approved methodology [AMS-1. D Grid Connected Renewable Electricity Generation V.18.0] and meets the methodology applicability conditions and has achieved the estimated GHG emission reductions, complies with the monitoring methodology and has calculated emission reductions estimates correctly and conservatively.

likely to generate GHG emission reductions amounting the to [25,746] estimated TCO_{2e}, as indicated in the PCN, which are additional to the reductions that are likely to occur in absence of the Project Activity and complies with all applicable UCR rules, including ISO 14064-2 and ISO 14064-3.

The Project Activity is not likely to cause any net-harm to the environment and/or society

The Project Activity complies with all the applicable UCR rules¹ and therefore recommends UCR Program to register the Project activity with

1

	above mentioned labels.
Project Verification Report, reference number and date of approval	Verification Report UCRReference number: 241 Date of approval: 25/08/2023
Name of the authorised personnel of UCR Project Verifier and his/her signature with date	Mr. Pankaj Kumar

PROJECT VERIFICATION REPORT

Executive summary

>> The proposed project activity involves construction and operation of 4 Small Scale Wind Power Projects (WPP) in the state of Karnataka in India.

The project activity has been essentially conceived to generate clean energy by utilizing the wind energy. It causes total minimum environmental impacts and in turn will lead to actual emission reduction of 12,724.11 tCO₂ over the entire monitoring period.

Total cumulative installed capacity of the project would be 14.2 MW with a total gross energy generation of 14,138 MWh. The Small-Scale wind power projects developed by M/S V.S. Lad & Sons, will deliver electricity to the buyer, through National transmission network.

The details of

Project	IPP	Capacity	Location	Net	Emission	Commissioned
,		, ,		Generation	Reduction	Date
1.2MW Wind	M/S V. S.	1.2 MW	Davangere	20,980	18,882	31/03/2006
Power	Lad &		district,			
Project in	Sons		Karnataka	MWh	tCO2e/yr	
Davangere						
6.25 MW	M/S V. S.	6.25	Gadag	64,410	57,969	10/08/2006
Wind Power	Lad & Sons	MW	district,			
Project in			Karnataka	MWh	tCO2e/yr	
Gadag						
3.0 MW Wind	M/S V.S.	3.0 MW	Chitradurg	20,710	18,639	28/03/2008
Power	Lad & Sons		district,			
Project			Karnataka	MWh	tCO2e/yr	
in Chitradurg						
3.75 MW	M/S V.S.	3.75	Bellary	35,279	31,751.1	30/09/2005
Wind Power	Lad & Sons	MW	district,			
Project in			Karnataka	MWh	tCO2e/yr	
Bellary.						

Proposed wind power project has evolved as a result of the policies of Government of India and Government of Maharashtra and Karnataka, which encourages energy development form renewable sources. These policies have given fresh impetus to wind power generation. Also, by virtue of being a wind power plant, the proposed plant can be instantly started, stopped and quickly adjusted for power generation corresponding to variations in power/energy releases.

The electricity produced by the project is directly contributing to climate change mitigation by reducing the anthropogenic emissions of greenhouse gases into the atmosphere by displacing an equivalent amount of power at grid.

Since the project activity will generate electricity through wind energy, a clean renewable energy source, it will not cause any negative impact on the environment and thereby contributes to climate change mitigation efforts.

Scope of Verification

The scope of the services for the project is to perform Project Verification of concerned Project Activity. The scope of verification is to assess the claims and assumptions made in the Project Concept Note (PCN) and Monitoring Report (MR) against the UCR criteria, including but not limited to, UCR program verification guidance document, UCR Standard, UCR Program Manual, and related rules and guidelines established under Program process.

Verification Process and Methodology

The verification process was undertaken by a competent verification team and involved the following,

Desk review of documents and evidence submitted in context of the reference rules and

- guidelines issued by UCR,
- Undertaking/conducting site visit/remote audit, interview or interactions with the representative of the project owners/representatives,
- Reporting audit findings with respect to clarifications and non-conformities and the closure of the findings, as appropriate and Preparing a draft verification opinion based on the auditing findings and conclusions
- Finalization of the verification opinion (this report)

Desk/Document review

A detailed desk review of the PCN, MR, Methodology and all other associated documentation and references took place in advance of the site visit, and additional documents that were not available for the desk review were requested for review during the site visit. Additional information can be required to complete the verification, which may be obtained from other public and reliable sources or through telephone and face to face interviews with key stakeholders (including the project developers and where necessary, Government and NGO representatives in the host country).

A list of all documents reviewed or referred to in the course of this verification is included in Appendix 3 below.

Follow up interviews/site visit

In view of COVID-19 pandemic, an on-site visit was not conducted as per UCR guidelines. The verifier conducted remote audit and had requested for site photographs, short videos. A remote interviews were conducted with the project owners and stakeholders.

No.	Interview		Date	Subject	Team member	
	Last name	First name	Affiliation			
1.	Kumar	Narendra	Kosher Climate	12/07/2023 to 14/07/2023	Project Implementation, Monitoring plan, Project Boundary, Eligibility criteria, Host country	Pankaj Kumar

No.	Interview			Date	Subject	Team member
	Last name	First name	Affiliation			
					requirements, Emission reduction calculations	
2.	K	Radhika	Kosher Climate		Local stakeholder	
3.	Uppin	Mahesh	Local Stakeholder		consultation	
4.	Shettar	Vikas	Local Stakeholder			
5.	Shetty	Suresh	Local Stakeholder			
6.	Khan	Ayub	Local Stakeholder			

Conclusion

Based on the work performed, the verifier concludes that the ":14.2 MW Wind Project in Karnataka" the information and data presented in the MR version 1.0 is in line with the Project Concept Note Version 2.0 dated 02/08/2022 and meets all relevant requirements of the UCR for UCR project activities. The UCR project activity correctly applies the methodology "AMS.I.D. – Grid connected renewable electricity generation" Version 18.0, leading to result in real, measurable and long-term emission reductions achieved for the current monitoring period.

For the current monitoring period, verified emission reductions achieved by the project activity were as below;

Start date of monitoring period	01/01/2014
End date of monitoring period	30/09/2022
Emission reductions achieved	12,724.11 tCO ₂ e

Project Verification team, technical reviewer and approver

>>

Project Verification team

,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,							
No.	Role	Last	First	Affiliation	Involvement in		
		name	name	(e.g. name of central or other office of UCR Project Verifier or outsourced entity)	Document review	Off-Site inspection	Interviews
1.	Team Leader	Kumar	Pankaj	Self	Yes	Yes	Yes

No.	Role	Type of	Last name	First name	Affiliation
		resourc			(e.g. name of
		е			central or other
					office of UCR
					Project Verifier or
					outsourced entity)
1.	Technical reviewer	Internal	Kumar	Pankaj	Self

Means of Project Verification

Desk/document review

>> A detailed desk review of the PCN, MR, methodology and all other associated documentation and references took place in advance of the remote audit, and additional documents that were not available for the desk review were requested for review during the remote audit. Additional information can be required to complete the verification, which may be obtained from other public and reliable sources or through telephone and face-to face interviews with key stakeholders (including the project developers and where necessary, Government and NGO representatives in the host country).

A list of all documents reviewed or referred to in the course of this verification is included in Appendix 3 below.

Off-site inspection

Date of offsite inspection:

No.	Activity performed Off-Site	Site location	Date
1.	a) An assessment of the implementation and operation of the project activity as per the PCN and UCR requirements	Davangere District, Karnataka, Gadag District, Karnataka,	12/07/2023 to 14/07/2023
	b) Verification of the project design, as documented is sound and reasonable, and meets the identified criteria of UCR Standard Requirements and associated guidance	Chitradurga Diastrict, Karnataka, Bellary District, Karnataka	
	c) Assessment to conformance with the certification criteria as laid out in the UCR Standards;		
	d) Evaluation of the conformance with the certification scope, including the GHG project and baseline scenarios, additionality; GHG sources, sinks, and reservoirs; and the physical infrastructure, activities, technologies and processes of the GHG project to the requirements of the UCR;		
	e) Evaluation of the calculation of GHG emissions, including the correctness and transparency of formulae and factors used; assumptions related to estimating GHG emission reductions; and		

	uncertainties; and determination whether the	
	uncertainties; and determination whether the	
	project could reasonably be expected to achieve	
	the estimated GHG reduction/removals.	
f)	Review of information flows for generating,	
	aggregating and reporting of the parameters to be	
	monitored	
g)	To confirm that the operational and data collection	
	procedures can be implemented in accordance	
	with the Monitoring Plan	
h)	Cross -check of information provided in the	
′	submitted documents and data from other	
	sources available at site	
i)	Review of calculations and assumptions made in	
"	determining the GHG data and estimated ERs,	
	•	
	and an identification of QA/QC procedures in	
	place to prevent, or identify and correct, any	
	errors or omissions in the reported monitoring	
	parameters	
j)	Interviews of local Stakeholders	

Interviews

No.		Interview		Date	Subject
	Last name	First name	Affiliation		
1.	Kumar	Narendra	Kosher Climate	12/07/2023 to	Project
2.	К	Radhika	Kosher Climate	14/07/2023	Implementation, Monitoring plan, Project Boundary, Eligibility criteria, Host country requirements, , Emission reduction calculations
3.	Uppin	Mahesh	Local Stakeholder		Project implementation,
4.	Shettar	Vikas	Local Stakeholder		monitoring, Local stakeholder
5.	Shetty	Suresh	Local Stakeholder		consultation
6.	Khan	Ayub	Local Stakeholder		

Sampling approach

Not applicable.

Clarification request (CLs), corrective action request (CARs) and forward action request (FARs) raised

Areas of Project Verification findings	No. of CL	No. of CAR	No. of FAR
Green House Gas (GHG)			
Identification and Eligibility of project type	-	-	-

General description of project activity	01	01	-
Application and selection of methodologies and standardized	-	-	-
baselines			
 Application of methodologies and standardized 	-	-	-
baselines			
 Deviation from methodology and/or methodological 	-	-	-
tool			
 Clarification on applicability of methodology, tool 	-	-	-
and/or standardized baseline			
 Project boundary, sources and GHGs 	-	-	-
- Baseline scenario	-	-	-
 Estimation of emission reductions or net 	-	-	-
anthropogenic removals			
- Monitoring Report	-	-	-
Start date, crediting period and duration	-	-	-
Environmental impacts	-	-	-
Project Owner- Identification and communication	-	-	-
Others (please specify)	-	-	-
Total	01	01	-

Project Verification findings

Identification and eligibility of project type

Means of Project Verification	The project has a 14.2 MW total installed capacity and hence is qualifies as a small scale project. This is confirmed based on the commissioning certificates and technical specifications.					
	Since the project is a small-scale project it has applied approved CDM small scale methodology AMS I.D, version 18.0 – Grid connected renewable energy generation.					
	The Project owner has used valid MR form available at the UCR website or the preparation of MR for the current project activity. The project has prepared MR in line with UCR guidance and requirements.					
Findings	No findings raised					
Conclusion	The UCR-approved format is used for description and the project meets the requirement of the UCR verification standard and UCR project standard. UCR project communication agreement was submitted to the verifier and the same has been verified. Methodology referenced and applied appropriately describing the project type. The eligibility of the project aggregator is verified using the UCR communication agreement, Project correctly applies the verification standard, UCR project standard, and UCR regulations. The project activity is overall meeting the requirements of the UCR Verification standard and UCR project standard					

General description of project activity

Means of Project Verification	The project activity involves the operation of a 14.2 MW of small-scale wind power project and its commissioning date was verified through the commissioning certificate of the project. The power evacuation at the substation is confirmed by the power purchase agreement. Assessment team conducted documentation review of the PCN against the UCR program verification standard version 2.0 and UCR project eligibility criteria version 6.0 and the UCR-PCN-FORM Version 1.0.			
	By checking the supporting documents, it is confirmed that the project is a newly built wind power project, located in India in the state of Karnataka, at Davangere (1.2 MW), Gadag (6.25 MW), Chitradurga (3.0 MW) & Bellary (3.75 MW). The approximate coordinates of the project locations are Davangere (i)14°15'27.3"N, 75°46'23.7"E & (ii)14°15'21.1"N, 75°46'23.4"E. Gadag (i)15°08'48.3"N, 75°48'14.6"E, (ii)15°08'18.4"N, 75°48'34.0"E, (iii)15°08'13.7"N, 75°48'38.3"E, (iv) 15°08'10.3"N, 75°48'43.8"E & (v)15°08'04.9"N, 75°48'48.4"E. Chitradurga (i)14°03'14.6"N, 76°26'18.9"E, (ii)14°03'00.3"N, 76°26'19.3"E. Bellary (i)14°58'12.0"N, 75°54'39.3"E, (ii)14°58'06.6"N, 75°54'43.5"E, (iii)14°58'01.4"N, 75°54'47.7"E respectively. Assessment team performed a remote inspection of project and confirmed that the			
	The Project is a wind power project, to utilize wind energy to generate zero carbon emission electricity which is mainly dominated by fossil fuel power output. The project includes integrated power transmission mechanism, high performance rotor blades, dual speed asynchronous generator, microprocessor based fully automatic control system with user friendly operation and central monitoring system. Quality, Safety and Health plan for construction, installation, commissioning and Operation & Maintenance. Microprocessor controlled high efficiency soft start. Active Yaw gear drives incorporating hydraulic yaw brakes.			
Findings	CL 01 & CAR 01 was raised and closed successfully. More information presented in appendix below.			
Conclusion	The description of the project activity is verified to be true based on the review of PCN, MR, Commissioning Certificate, Purchase Order Copies and power purchase agreements.			

Application and selection of methodologies and standardized baselines

(.a.i) Application of methodology and standardized baselines

Means of Project Verification	The project has taken the reference of CDM methodology A.M.S I.D. CDM website is referred to check the latest version of the methodology. For the applicability mentioned in the PCN and MR, turbine Specification, and commissioning certificate
Findings	No findings raised
Conclusion	The methodology applied is appropriately meeting the requirements of UCR and its standardized baseline. The methodology version is correct and valid. The referenced methodology is applicable to project activity.

(.a.ii) Clarification on applicability of methodology, tool and/or standardized baseline

Means of Project Verification	The documents reviewed are A.M.S I. D "Grid connected renewable electricity generation" version 18, UCR Program standard, and UCR Verification Standard
Findings	No findings raised
Conclusion	The emission factor considered for the calculation of the emission reductions is verified with the UCR Program Standard. The total installed electrical energy generation capacity of the project equipment does not

exceed 15 MW thus meeting the requirement of small-scale projects. It				
was confirmed that application of methodology and tools is correctly				
described in the MR submitted				

(.a.iii) Project boundary, sources and GHGs

Means of Project Verification	Project owner has considered project boundary As per applicable methodology AMS-I.D. Version 18, "The spatial extent of the project boundary includes the project power plant and all power plants connected physically to the electricity system that the project power plant is connected to." Review of PCN and MR confirms that project sites and Indian electricity grid system is considered as a project boundary which is appropriate.
Findings	No findings raised
Conclusion	The project boundary is correctly defined in the PCN and MR. GHG sources are correctly identified and reported. The project meets the requirements of UCR project standard, Verification standard and methodology requirements for a boundary, GHG sources.

(.a.iv) Baseline scenario

Means of Project Verification	As per the applied methodology AMS.I.D Grid connected renewable electricity generation Version 18.0 the baseline scenario is as following:					
	The baseline scenario is that the electricity delivered to the grid by the project activity would have otherwise been generated by the operation of grid-connected power plants and by the addition of new generation sources into the grid.					
	Remote audit conducted and document review showed that in absence of the project activity, the generated electricity would have been supplied by the Indian grid which is dominated by fossil fuel fired plants.					
Findings	No findings raised					
Conclusion	The approved baseline methodology has been correctly applied to identify a realistic and credible baseline scenario, and the identified baseline scenario most reasonably represents what would occur in the absence of the proposed UCR project activity.					
	All the assumption and data used by the project participants are listed in the PCN and/or supporting documents. All documentation relevant for establishing the baseline scenario are correctly quoted and interpreted in the PCN. Assumptions and data used in the identification of the baseline scenario are justified appropriately, supported by evidence and can be deemed reasonable. Relevant national and/or sectoral policies and circumstances are considered and listed in the PCN.					

(.a.v) Estimation of emission reductions or net anthropogenic removal

Means of Project Verification

The verification team has assessed the calculations of baseline emissions and emission reductions. Corresponding calculations have been carried out based on calculation spread sheet. The parameters and equations presented in the PCN, as well as other applicable documents, have been compared with the information and requirements presented in the methodology and respective tools. An equation comparison has been made to ensure consistency between all the formulae presented in the calculation files and in the PCN, methodology, and tools.

The assumptions and data used to determine the emission reductions are listed in the PCN and all the sources have been checked. Based on the information reviewed it is confirmed that the sources used are correctly quoted and interpreted in the PCN.

The values presented in the PCN are considered reasonable based on the documentation and references reviewed and the results of the interviews.

The baseline methodology has been applied correctly according to requirements.

The estimate of the baseline emissions are considered correct as the calculations have been reproduced by the verification team with the attainment of the same results. The algorithms for the determination of the baseline, project, and leakage are discussed in the following sections.

A "grid emission factor" refers to a CO2 emission factor (tCO2/MWh) which will be associated with each unit of electricity provided by an electricity system. The UCR recommends an emission factor of 0.9 tCO2/MWh for the 2014-2020 years as a fairly conservative estimate for Indian projects not previously verified under any GHG program. Also, for the vintage 2021, the combined margin emission factor calculated from CEA database in India results into higher emission than the default value. Hence, the same emission factor has been considered to calculate the emission reduction under conservative approach.

Net GHG Emission Reductions and Removals

 $ER_y = BE_y - PE_y - LE_y$

Where:

 $ER_y = Emission reductions in year y (tCO2/y)$

 $BE_y = Baseline Emissions in year y (t CO₂/y)$

 $PE_y = Project emissions in year y (tCO₂/y)$

 LE_y = Leakage emissions in year y (tCO2/y)

Baseline Emissions

Baseline emissions include only CO₂ emissions from electricity generation in power plants that are displaced due to the project activity. The methodology assumes that all project electricity generation above baseline levels would have been generated by existing grid-connected power plants and the addition of new grid-connected power plants.

The baseline emissions are to be calculated as follows:

 $BEy = EG PJ,y \times EFgrid,y$

Where:

 BE_y = Baseline emissions in year y (t CO2)

EGPJ,y = Quantity of net electricity generation that is produced and fed into the grid as a result of theimplementation of this project activity in year y (MWh)

EFgrid,y = UCR recommended emission factor of 0.9 tCO2/MWh has been considered, this is conservative as compared to the combined margin grid emission factor which can be derived from Database of Central Electricity Authority (CEA), India. (Reference: General Project Eligibility Criteria and Guidance, UCR Standard, page 4)

Project Emissions

As per paragraph 39 of AMS-I.D. (Version 18.0, dated 28/11/2014), , only emission associated with the fossil fuel combustion, emission from operation of geo-thermal power plants due to release of non-condensable gases, emission from water reservoir of Hydro should be accounted for the project emission. Since the project activity is a wind power project, project emission for renewable energy plant is nil.

Hence, $PE_y = 0$

Leakage

As per paragraph 42 of AMS-I.D. version-18, 'If the energy generating equipment is transferred from another activity (biomass), leakage is to be considered.' In the project activity, there is no transfer of energy generating equipment and therefore the leakage from the project activity is considered zero

Hence, $LE_v = 0$

The actual emission reduction achieved during the first CoU period shall be submitted as a part of first monitoring and verification. However, for the purpose of an ex-ante estimation, following calculation has been submitted:

1.2 MW Wind Power Project in Davangere

Estimated annual baseline emission reductions (BE_y)

- =20,980 MWh/year \times 0.9 tCO₂/MWh
- = 18,882 tCO₂/year (i.e., 18,882 CoUs/year)

6.25 MW Wind Power Project in Gadag

Estimated annual baseline emission reductions (BE_y)

- = 64,410 MWh/year x 0.9 tCO₂/MWh
- = 57969 tCO2/year (i.e., 57969 CoUs/year)

3.0 MW Wind Power Project in Chitradurg

Estimated annual baseline emission reductions (BE_y)

- =20710 MWh/year \times 0.9 tCO2/MWh
- =18639 tCO2/year (i.e., 18639 CoUs/year)

3.75 MW Wind Power Project in Bellary

Estimated annual baseline emission reductions (BE_y)

- = 35,279 MWh/year × 0.9 tCO2/MWh
- = 31751.1 tCO2/year (i.e.,31,751.1 CoUs/year)

Project	(MWh/)		Emission Reduction (tCO2/	
1.2MW Wind Power	20,980	0.9	18,882	
Project in Davangere				
6.25 MW Wind Power	64,410	0.9	57969	
Project in Gadag				
3.0 MW Wind Power	20,710	0.9	18639	
Project in Chitradurg				
3.75 MW Wind Power	35,279	0.9	31,751.1	
Project in Bellary.				
Total	141379		127241.1	

Yearly emission reductions calculation for the monitoring period is given in the table below.

		Net Ene	rgy Expo	Grid Emissio			
Monitoring Period	1.20 MW Davangere	6.25 MW Gadag	3.75 MW Bellary	3.00 MW Chitradurg	Total	Emission Factor	Reduction (tCO2)
01-01-2014 to 31-12- 2014	1666	0	0	0	1666	0.90	1499.4
01-01-2015 to 31-12- 2015	1224	3982	1723	862	7791	0.90	7011.9
01-01-2016 to 31-12- 2016	8550	10905	5874	3439	28768	0.90	25891.2
01-01-2017 to 31-12-	3007	7024	4045	2156	16232	0.90	14608.8

				Total	141379		127241.1
01-01-2022 to 30-09- 2022	1066	7548	5417	3287	17318	0.90	15586.2
01-01-2021 to 31-12- 2021	1134	9280	4324	2892	17630	0.90	15867
01-01-2020 to 31-12- 2020	1399	8812	4405	1869	16485	0.90	14836.5
01-01-2019 to 31-12- 2019	1589	8134	4684	3159	17566	0.90	15809.4
01-01-2018 to 31-12- 2018	1345	8725	4807	3046	17923	0.90	16130.7
2017							

Findings

Conclusion

No findings raised

In summary, the calculation of emission reductions was correctly demonstrated by the PP according to the methodology AMS.I.D. - Grid connected renewable electricity generation Version 18.0 and its tool "Tool to calculate the emission factor for an electricity system" Version 07.0.

It is confirmed by Assessment team that:

(a) All assumptions made for estimating GHG are listed in the PCN; (b) All documentation used by the project participants as the basis for assumptions and source of data is correctly quoted and interpreted in the PCN; (c) All values used in the PCN including GWPs are considered reasonable in the context of the proposed UCR project activity; (d) The methodologies and, where applicable, the standardized baselines and the other methodological regulatory documents have been applied correctly to calculate baseline, project and leakage GHG emissions, as well as GHG emission reductions; (e) All estimates of the baseline GHG emissions can be replicated using the data and parameter values provided in the PCN; (f) The sampling efforts were undertaken in accordance with the "Standard: Sampling and surveys for UCR project activities and programme of activities", where the applied methodologies require that the data and parameters be determined in accordance with this standard.

(.a.vi) Monitoring Report

Means of Project Verification

Parameters determined ex-ante

The following parameters are determined ex-ante and verified by the verification team:

The baseline emission factor of the project is reported to be determined ex-ante and would remain fixed for the crediting period, which is calculated as a combined margin (CM), consisting of the combination of OM and BM emission coefficient. The parameters applied in the calculation were validated by the verification team.

The verification team confirms that all relevant parameters have been sufficiently considered and the values of the parameters are real, measurable and conservative.

Parameters monitored ex-post

According to the approved methodology AMS.I.D. - Grid connected renewable electricity generation Version 18.0, the following parameters will be monitored:

Parameter	Description
EGPJ,facility,y	Quantity of net electricity generation supplied by the projectplant/unit to the grid in year y
EGPJ,output,y	Electricity supplied by the proposed CDM project to the grid in year y
EGPJ,input,y	The electricity used by the proposed CDM project and input from the grid in year y

The values of the parameters monitored were checked against submittedJoint Meter Readings and invoices and were found correct.

Management system and quality assurance

The monitoring plan presented in the PCN complies with the requirements of the applicable methodology. The verification team has verified all parameters in the monitoring plan against the requirements of the methodology and no deviations have been found.

The management system and quality assurance procedures have been reviewed by the verification team through document review and interviews with the project participant. The project participant would train all the monitoring staffs are trained against with related requirement; the training guidelines and monitoring manual are saved and verified.

The monitoring plan outlines in the PCN includes:

- Monitoring Organization
- Monitoring apparatus and installation:
- Calibration
- Data collection:
- Data Management system

The electricity exported and imported by the project will be continuously measured by the meters and it would be monthly reported.

	Calibrations of the meters will be carried out by a qualified third party periodically. Cross-check measurements include the comparison with the record document confirmed by EDL. The submitted calibration certificates were checked and it was confirmed that the calibrations are conducted periodically as specified in the PCN i.e. at least once in 5 years. No delay in calibration is observed and no meter change has taken place during the current monitoring period.
Findings	No findings raised
Conclusion	The verification team is convinced of compliance of the monitoring plan with the requirements of the monitoring methodology AMS.I.D Grid connected renewable electricity generation Version 18.0. During the onsite assessment, the verification team interviewed the PP that the monitoring arrangements described in the monitoring plan are feasible within the project design.
	The monitoring parameter reported in MR adequately represents the parameters relevant to emission reduction calculation. The calibration report ensures the accuracy of the data reported. The number of CoUs generation is calculated based on this accurately reported data. The calculation was done using an excel sheet where all the parameters were reported. The emission factor for electricity is as per UCR standards. In the monitoring report, emission reduction calculations are correctly calculated and reported. The monitoring report meets the requirements of UCR project verification requirements.

Start date, crediting period and duration

Means of Project Verification	The start date and crediting period of project activity was checked based on the commissioning certificate, purchase orders for the turbines, PCN, MR and detailed project report.
Findings	No findings raised
Conclusion	The project has chosen crediting period start date as 01/01/2014. The crediting period is chosen as 01/01/2014 to 30/09/2022.

Positive Environmental impacts

Means of Project Verification	PP has not claimed any separate positive environmental impact. The project being renewable energy project will reduce fossil fuel use through replacement of the same.
Findings	No findings raised
Conclusion	The project is a renewable energy project and reduces the environmental burden by reducing the dependence on fossil fuel based power plants.

Project Owner- Identification and communication

Means of Project Verification	different locations	owned and	operated by	
	Project	IPP	Capacity	Location
	1.2MW Wind Power Project in Davangere	M/S V. S. Lad &	1.2 MW	Davangere district,
	in Davangoro	Sons		Karnataka
	6.25 MW	M/S V. S. Lad	6.25	Gadag
	Wind Power	& Sons	MW	district,
	Project in			Karnataka
	Gadag			
	3.0 MW Wind	M/S V. S. Lad	3.0 MW	Chitradurg
	Power Project	& Sons		district,
	in Chitradurg			Karnataka
	3.75 MW	M/S V. S. Lad	3.75	Bellary

	Wind Power	& Sons	MW	district,
	Project in			Karnataka
	Bellary.			
	Kosher climate is acting as an	aggregator for the	ese projects	. The
	submitted commissioning certi-	ficates, agreemer	nts, joint met	ter readings
	confirm the ownership of the p	rojects by the pro	ject owner.	
Findings	No findings raised			
Conclusion	The project owner was identified through a communication agreement			
	signed between project own			
	purchase orders and commiss			
	legal document like Power Pu			
	clearly establishes the proj			
	communication correctly mee	t the requiremer	nt of projec	t verification
	and UCR project standard.			

Positive Social Impact

Means of Project Verification	Project has provided temporary employment to local people during its installation and commissioning. Also post commissioning some of people have employed permanently and local people were engaged leading to social financial benefit to surrounding. Overall social impact of project implementation is positive on the surrounding area
Findings	No findings raised
Conclusion	Project has overall positive social impact

Sustainable development aspects (if any)

Means of Project Verification	Not applicable
Findings	Not applicable
Conclusion	Not applicable

Internal quality control

>> The verifier confirms that,

- Due professional care has been taken while reviewing the submitted document.
- There is no conflict of interest as the verifier has no other engagement with either the aggregator or project owner directly or indirectly.
- Verification team consists of experienced personnel.

Project Verification opinion

Assessment team conducted documentation review the PCN against the UCR program verification standard version 2.0 and UCR project eligibility criteria version 6.0 and the UCR-PCN-FORM Version 1.0.

It is confirmed that the project is a newly built wind power project, located in India in the state of Karnataka, at Davangere (1.2 MW), Gadag (6.25 MW), Chitradurga (3.0 MW) & Bellary (3.75 MW). The approximate coordinates of the project locations are Davangere (i)14°15'27.3"N, 75°46'23.7"E & (ii)14°15'21.1"N, 75°46'23.4"E. Gadag (i)15°08'48.3"N, 75°48'14.6"E, (ii)15°08'18.4"N, 75°48'34.0"E, (iii)15°08'13.7"N, 75°48'38.3"E, (iv) 15°08'10.3"N, 75°48'43.8"E & (v)15°08'04.9"N, 75°48'48.4"E. Chitradurga (i)14°03'14.6"N, 76°26'18.9"E, (ii)14°03'00.3"N, 76°26'19.3"E. Bellary (i)14°58'12.0"N, 75°54'39.3"E, (ii)14°58'06.6"N, 75°54'43.5"E, (iii)14°58'01.4"N, 75°54'47.7"E respectively.

Assessment team performed a remote audit and confirmed that the location described in the PCN is accurate. The verification was performed on the basis of UCR requirements, and host country criteria, as well as criteria given to provide for consistent project operations, monitoring and reporting.

The verification consisted of the following three phases: i) desk review of the PCN, MR and additional background documents; ii) follow-up interviews with project stakeholders; iii) resolution of outstanding issues and the issuance of the final verification report and opinion.

01 CL and 01 CAR were raised during the document review. After communication with the PP, the project participants revised the PCN and all CARs and CLs were closed.

The project correctly applies the approved baseline and monitoring methodology AMS-I.D. - Grid connected renewable electricity generation, Version 18.0.

The monitoring plan provides for the monitoring of the project's emission reductions. The monitoring arrangements described in the monitoring plan are feasible within the project design, and that the project participants are able to implement the monitoring plan. Given that the project is implemented and maintained as designed, the project is likely to achieve the estimated emission reductions of 127241.1 tCO2eq during the eight years, nine months of its first renewable crediting period.

The review of the project design documentation and the subsequent follow-up interviews have provided assessment team with sufficient evidence to determine the fulfilment of stated criteria. In our opinion, the project meets all applicable UCR requirements. Assessment team thus requests the registration of the proposed UCR project activity.

Abbreviations

Abbreviations	Full texts	
ACM	Approved Consolidated Methodologies	
UCR	Universal Carbon Registry	
PCN	Project Concept Note	
MR	Monitoring Report	
t	Tonne	
ISO	International Organization for Standardization	
DNA	Designated National Authority	
CER	Certified Emission Reductions	
NGO	Non-Governmental Organization	
FSR	Feasibility Study Report	
IEE	Initial Environmental Examination	
CAR	Corrective Action Request	
GHG	Greenhouse Gas	
Gwh	Gigawatt Hours	
Mwh	Megawatt Hours	
CO2	Carbon Dioxide	
CH4	Methane	
N2O	Nitrous Oxide	

Competence of team members and technical reviewers

>> Mr. Pankaj Kumar worked as team leader – Bihar for South Asia Climate Proofing and Growth Development (CPGD) – Climate Change Innovation Programme (CCIP) supported by DFID that seeks to mainstream climate change resilience into planning and budgeting at the national and sub-national level in India, Pakistan, Nepal, and Afghanistan. Pankaj Kumar has worked previously with IL&FS Infrastructure Development Corporation and BUIDCO (Bihar Urban Infrastructure Development Corporation), Govt. Of Bihar as Environmental Specialist for WB & ADB funded projects. Prior to this, he

worked with Carbon Check (UNFCCC accredited DoE), Johannesburg, RSA as Team Leader for validation, verification of around 100 GHG projects in Asia, Africa, USA, Asia Pacific & Americas. Pankaj is accredited Lead Auditor, Validator, Verifier and Technical Expert for Sectoral Scope/Technical Area – 1.1, 1.2, 3.1 & 13.1 by UNFCCC DoE (Designated Operational Entity), APPLUS, Spain. He is also member of task force on climate change & human health, Health Department, GoB and on roster of UNICEF's WASH experts.

He is an experienced, qualified and result oriented Environment Professional having more than 14 yrs. Of relevant experience in Climate Change (Mitigation &Adaptation), Environmental Due Diligence, Disaster Risk Reduction, Validation and Verification of GHG project under CDM, Verified Carbon Standard, Gold Standard & Social Carbon Standard, Brazil. He provides technical support for environmental investigative, consultative and remedial projects involving air, water and soil, Waste management, EIA, Environmental Compliance, ISO 14001, OHSAS 18001, GHG accounting (ISO 14064) and Carbon foot printing.

Pankaj Kumar is Masters in Environment Management from Forest Research Institute (University), I. C. F. R. E, Dehradun, which is Centre of Excellence in South East Asia for Forestry education & researchand PGDEL from National Law School of India University, Bangalore (India).

Document reviewed or referenced

No.	Author	Title	References to the document	Provider
1	NA	Communication agreement		Project Owner
2	NA	Project Concept Note		Aggregator
3	NA	Monitoring report		Aggregator
4	NA	Emission reduction sheet		Aggregator
5	NA	Declaration on avoidance of double counting		Aggregator
6	NA	Commissioning Certificates for the hydro power plants		Aggregator
7	NA	Power purchase agreement/wheeling agreement		Aggregator
8	NA	Joint Meter Readings/invoices for the complete monitoring period		Aggregator
9	NA	Calibration certificates for energy meters		Aggregator
10	NA	Purchase order for turbine/generator		Aggregator
11	NA	CEA database version 9.0		Central Electricity Authority, Government of India
12		UCR Program manual version 5 UCR COU standard version 6 UCR Verification standard version 2 UCR terms and conditions		Universal Carbon Registry
13	NA	CDM approved methodology – AMS I. D version 18.0		UNFCCC

Clarification request, corrective action request and forward action request

Table 1. CLs from this Project Verification

CL ID	01			Date: 24/05/2023
Description of CL				

- 1. On page 01, First Cou Issuance period is mentioned as 8 years 5 months in PCN while in MR it is mentioned as 8 years 9 months. Issuance period date is same in PCN and MR 01/01/2014 to 30/09/2022.
- 2. In basic information of MR project participant name is not matching with that of PCN. In PCN it is mentioned as M/S V.S. Lad & Sons while in MR it is mentioned as V. S. Lad & Sons.
- 3. In section A.5. of PCN and A.3. of MR project participant name is not matching with that of the basic information. In basic information it is mentioned as M/S V.S. Lad & Sons while in sections A.5. and A.3 it is mentioned as V. S. Lad & Sons.
- 4. In section A.4. of MR in applicability table, under point 4, the project case is mentioned as the run-off river type hydro project which is not the project case.

Date: 20/07/2023

5. In section B.9. of PCN, First Issuance Period does not match with that mentioned on cover page.

Project Owner's response

- 1. 1st page is corrected in PCN.
- 2. MR is corrected as M/S V.S. Lad & Sons which is in-line with PCN.
- 3. A.3 of MR is corrected as M/S V.S. Lad & Sons. In PCN A.5 is now corrected.
- 4. In section A.4 of MR; point 4 is corrected as "Project is Wind and hence this criterion is not applicable."
- 5. PCN cover page is updated as 8 years 9 months.

Documentation provided by Project Owner

- 1. Version.2 of PCN
- 2. Updated MR

UCR Project Verifier assessment

- **Date:** 25/08/2023 1. As suggested PP has done the changes in issuance period in 1st page of PCN. Hence, this part of CL has been closed.
- 2. Project participant name in MR is now in line with that of in PCN. Hence, this part of CL has been closed.
- 3. Project participant name is now corrected in section A.3 of MR & section A.5 of PCN. Hence, this part of CL has been closed.
- Project case is changed in section A.4 of MR. Hence, this part of CL has been closed.
- 5. PCN cover page is updated in line with section B.9 of PCN. Hence, this part of CL has been closed.

Table 2. CARs from this Project Verification

CAR ID 01 **Date:** 24/05/2023 **Description of CAR**

- 1. In section B.5. of PCN and C.5. of MR under project emissions, the project type is mentioned as run of river project which is not the project case.
- 2. In section C.5. of MR. in 2nd paragraph under leakage, it is mentioned that the calculations are ex ante calculations.
- 3. Emission reductions for year 01/01/2016 to 31/12/2016 are 25,891.2 tCO₂ as per ER sheet while in MR basic information table it is mentioned as 27,891.2 tCo₂.
- 4. In section A.1 of MR the actual emission reductions are mentioned as 25,746 tCO2 per year while as per ER sheet actual reductions are 127,241.1 tCO₂ for the entire monitoring period.
- 5. In section A.1 of MR the total energy generation is mentioned as 28,608 MWh while as per ER sheet total energy generation is 141,379 Mwh for the entire monitoring period.
- 6. In section C.5. of MR, the last table which mentions the net power generation and emission reduction of individual wind power station, the unit of power generation is mentioned as Mwh/year and the unit of emission reductions is mentioned as tCO₂/year. But the power generation and emission reductions are of the entire monitoring period.
- 7. In section B.5. of PCN, the last table which mentions the net power generation and emission reduction of individual wind power station, the unit of power generation is mentioned as Mwh/year and the unit of emission reductions is mentioned as tCO₂/year. But the power generation and emission reductions are of the entire monitoring period.
- 8. In section C.10. of MR in 2nd table (Data and Parameters to be monitored (ex-post monitoring values)) the value of net electricity generated is mentioned as 150,670 MWh while as per ER sheet it is 141,379 MWh.
- 9. In section B.8. of PCN the 2nd table is mentioned as Data and Parameters to be monitored (ex-post monitoring values) but it should be ex-ante monitoring values.

Project Owner's response Date: 20/07/2023

- 1. Section B.5 is updated in PCN. Section C.5 in MR is updated "As per paragraph 39 of AMS-I.D. version-18, only emission associated with the fossil fuel combustion, emission from operation of geothermal power plants due to release of non-condensable gases, emission from water reservoir of Hydro should be accounted for the project emission. Since the project activity is a wind power project, project emission for renewable energy plant is nil.
- 2. Section C.5 of MR is correct "As per paragraph 42 of AMS-I.D. version-18, 'If the energy generating equipment is transferred from another activity (biomass), leakage is to be considered.' In the project activity, there is no transfer of energy generating equipment and therefore the leakage from the project activity is considered zero".
- 3. Emission reduction for the year 01/01/2016 to 31/12/2016 is corrected in MR as per ER sheet as 25,891.2 tCO2.
- 4. Section A.1 of the MR is updated with the actual emission reductions as 12,724.11 tCO2 per year which is in line with the total actual emission reduction in ER for the entire crediting period.
- Section A.1 of MR, the total energy generation is updated as 14,138 MWh which is in line with the total energy generation 141,379 MWh in ER.
- Section C.5 of MR, the table is updated.
- 7. The table in Section B.5. of PCN is updated for the crediting period.
- 8. Section C.10 of MR, 2nd table where the value of net electricity generated is corrected as 141,379MWh which is in line with ER.
- 9. The actual net electricity generated is sourced from monthly generation reports. electricity generation will be monitored after the project starts its commissioning. Hence, this parameter is considered to be ex-post and not ex-ante.

Documentation provided by Project Owner

- 1. PCN Version.2
- 2. Update MR

UCR Project Verifier assessment

- Date: 25/08/2023 1. PP has updated section B.5 in PCN & section C.5 in MR as per the valid project case. Hence, this part of CAR has been closed.
- 2. In section C.5 of MR, PP has corrected the leakage emission part. Hence, this part of CAR has been closed.
- 3. Emission reductions for the year 01/01/2016 to 31/12/2016 have been updated in MR in line with the ER sheet. Hence, this part of CAR has been closed.
- 4. In section A.1 of MR actual emission reductions are updated in line with the ER sheet. Hence, this part of CAR has been closed.
- 5. In section A.1 of MR total energy generation is updated in line with the ER sheet. Hence, this part of CAR has been closed.
- 6. In section C.5 of MR, units of both emission reduction and energy generation have been corrected. Hence, this part of CAR has been closed.
- 7. In section B.5 of PCN, units of both emission reduction and energy generation have been corrected. Hence, this part of CAR has been closed.
- 8. In section C.10 of MR value of net energy generation is updated in line with the ER sheet. Hence, this part of CAR has been closed.
- Clarification regarding section B.8 of PCN has been done. Hence, this part of CAR has been closed.

Table 3. FARs from this Project Verification

FAR ID	XX	Section no.	Date: DD/MM/YYYY	
Description	of FAR			
Project Own	er's response		Date: DD/MM/YYYY	
Documentation provided by Project Owner				
UCR Project Verifier assessment Date: DD/MM/YYYY				
_			•	